



Eletrobras
Eletronuclear


Updating Nuclear Power Program in Brazil After Fukushima

LAS-ANS SYMPOSIUM 2012
July 3rd 2012



FUKUSHIMA BRINGS 2 NEWS FOR WORLD NUCLEAR INDUSTRY

A BAD ONE



OTHER NOT SO BAD




FUKUSHIMA BRINGS 2 NEWS

THE BAD NEWS




**SEVERE ACCIDENTS HAPPEN
EVEN AFTER ALL POST-TMI, POST-
CHERNOBYL AND OPERATIONAL
EXPERIENCE FEEDBACK COUNTER-
MEASURES**




FUKUSHIMA BRINGS 2 NEWS

THE NOT SO BAD NEWS



Preliminary dose estimation

from the nuclear accident after the 2011 Great East Japan Earthquake and Tsunami





published
May 24th 2012



THEY ARE NOT SO "CATASTROPHIC"
THE OBJECTIVELY MEASURED HARM FOR PUBLIC AND ENVIRONMENT CAUSED DOES NOT ADHERE TO THE HYPERBOLIC LANGUAGE OFTEN USED

FALLOUT COMPARISONS


New data from Fukushima show caesium-137 levels approaching those of Chernobyl — but over a much smaller area.





Fukushima Response Plan

(submitted to Brazilian Nuclear Authority in December 2011)

 Eletrobras Eletronuclear	RELATÓRIO	CLASSE	Nº
		3	P-001/11
ELETROBRAS ELETRONUCLEAR PLANO DE RESPOSTA A FUKUSHIMA (aprovado pela RDE nº 1054.001/11 de 30.11.2011)		PÁGINA	1 / 44
		LOCAL/DATA	Rio, 28.11.2011
		REDATOR	Paulo Carneiro
		U.O./TEL.	DT / 7053
REFERÊNCIA	CNAAA	CÓDIGO ARQUIVO	P-001/11

56 initiatives (studies and projects)

Performance of Stress Tests

Around US\$ 250 million to be applied from 2011 to 2015

High priority inside the organization

Nº DE PÁGINAS	ANEXOS	(NOS RELATÓRIOS DE REUNIÃO INDICAR, INICIALMENTE, NO SUMÁRIO: LOCAL, DATA, COORDENADOR, PARTICIPANTES E DURAÇÃO)	Para ser providenciado Para conhecimento prazos
44	3		
Sumário A elaboração do PLANO DE RESPOSTA A FUKUSHIMA apresentado neste Relatório foi determinada pela Diretoria Executiva, como uma das atribuições do Comitê Gerencial de Resposta a Fukushima, instituído pela CGE nº 038/11 de 20/09/2011.			



Fukushima Response Plan

(submitted to Brazilian Nuclear Authority in December 2011)

General Time Scheduling – Main Events

Year	Protection Against Risk Events	Cooling Capacity	Mitigation of Radiological Consequences
2012	Conclusion of more relevant site studies (landslides, waves and external flooding)	Conclusion of studies on reactor and fuel pool cooling	Ordering of all systems and equipment for containment atmosphere control
2013	Conclusion of evaluation of design margins for earthquake	Implementation of mobile equipment for power and water supply (first quarter)	
2014	Conclusion of all plant interventions related to eternal events	Conclusion of SAMGs implementation for Angra 2 Conclusion of all plant interventions related to cooling capacity	Conclusion of Implementation of all systems and equipment for containment atmosphere control
2015	Conclusion of all initiatives of Fukushima Response Plan		



Fukushima Response Plan

(submitted to Brazilian Nuclear Authority in December 2011)

Budget for Plan Execution

Plant Unit	Budget for Scope Defined	Cost Estimation for interventions not yet defined	Total
Angra 1	25.000.000	29.000.000	54.000.000
Angra 2	23.000.000	10.000.000	33.000.000
Central	52.000.000	110.000.000	162.000.000
TOTAL	100.000.000	149.000.000	249.000.000

	2011	2012	2013	2014	2015
Budget for Scope Defined	2.000.000	16.000.000	16.000.000	50.000.000	16.000.000
Cost Estimation for Interventions not Defined	0	2.000.000	40.000.000	76.000.000	31.000.000

Stress Tests for Angra 1 and 2



Evaluación de Resistencia de las Centrales Nucleares en los Países Miembros del FORO Iberoamericano de Organismos Reguladores, Radiológicos y Nucleares

Septiembre 2011



According to specification issued by Iberoamerican Forum of Regulatory Bodies, Nuclear and Radiological (request from CNEN in January 2012)

Compliance with WENRA Specification for Stress Tests



Submitted to CNEN on April 2nd, 2012



Stress Tests for Angra 1 and 2

Evaluation of Loss of Heat Sink Condition

Favorable Angra conditions:

- water intake structures in area of protected sea water (Ilha Grande Bay);
- water intake structures protected by jetty 8,0m high above average seawater level;
- very low probability of water intake blockage to the extent of impairing minimum flow for residual heat removal;
- water availability at site enough for long term cooling through steam generators (about 30 hours SG feeding without tank refilling);
- possibility of feeding steam generators by fully passive means (fire fighting system, water reservoir of 6,000m³ at 110m height);



Stress Tests for Angra 1 and 2

Loss of Fuel Pool Cooling

Temperature Increase after Loss of Cooling Function

Unit	Plant condition	Time until start boiling	Time until fuel element exposure
Angra 1	Power Operation	18h	190h
	Refuelling (*)	9h	63h
Angra 2	Power Operation	23h	155h
	Refuelling (*)	5h	35h

(*) limit condition, full core unloaded and full occupation of pool racks



Stress Tests for Angra 1 and 2

Coping with SOB and LUHS: Additional Means

Under final dimensioning and specification:

- one mobile diesel generator for each unit as alternative power supply for safety systems (~ 1,000 to 1,800kVA);
- one mobile diesel generator for each unit for batteries reloading and supply of small components (borating pump)(~250kVA);
- two mobile water pumps for each unit as an alternative mean for feeding the steam generators (27kg/s and 75m);
- two mobile water pumps for each unit for refilling water reservoirs and pools (20kg/s and 20m);
- one mobile air compressor for Angra 1 as an alternative mean for remote actuation of main steam and feedwater valves;
- mobile fuel pool cooling unit for Angra 1 (design only one train)



Stress Tests for Angra 1 and 2

Mitigation of Consequences

Severe Accident Management Guidelines - SAMG

- Angra 1 SAMG prepared based on standard PWR SAMG developed by Westinghouse Owner's Group; plant personnel training on going;
- Angra 2 SAMG under preparation by AREVA;
- state of art of Westinghouse Owner's Group and AREVA SAMG does not consider lessons learned from Fukushima;
- revision of Angra 1 SAMG for incorporating Fukushima experience after reevaluation by "PWR Owners Group" is available;
- Angra 2 SAMG will already consider at least partially mitigation strategies under implementation on Angra 2;
- contracting of containment venting and H2 recombiners on going;



Stress Tests for Angra 1 and 2

Management of Emergency Conditions

Local Emergency Plan complies with Brazilian and international requirements;

the following opportunities for improvement have been addressed:

- improvement of communication between Emergency Centers;
- construction and enlargement of wharfs in the vicinity of the plant (sea transportation of personnel, equipment and materials);
- modification of radiological protection procedures for application in severe accident conditions (participation in the initiative of ISOE/NEA/OECD/IAEA).



DECENIAL ENERGY PLAN 2020

No changes for Angra 3, but no new build



ANGRA 3: 1.405 MW AREVA PWR



4.000 workers

30/06/2012



ANGRA 3
1.405 MW
2015





NATIONAL ENERGY PLAN 2030

1 - 2 year delay minimum

1. **Update 2035 (more nuclear?)**
 - Was not be presented in 2011, as planned – only this year
2. **Candidate areas National Atlas**
 - Would be presented May 2011
 - Will not be presented in 2011, as planned – only in 2012 (?)
3. **Site selection field works**
 - Would be started end 2011
 - Delayed (2013?)



NUCLEAR POTENTIAL ATLAS 40 CANDIDATE AREAS

2016-2020	2021-2025	2026-2030	2016-2030
1.000 MW NE 1	1.000 MW NE 2	2.000 MW SE 1+SE 2	4.000 MW

**1) Northeast
2.000 MW**

**2) Southeast
2.000 MW**



Thank you!

LAS ANS SYMPOSIUM 2012
July 3rd 2012