

**NPP PROJECT ATUCHA II - ARGENTINE**  
**(Current situation May 2008)**

**LAS/ANS SYMPOSIUM 2008**

**Reactivation of Nuclear Power Plants Construction in Latin America**

**16-20 June 2008**  
**Rio de Janeiro, Brazil**

Eng. MIGUEL ANGEL BAEZ  
NUCLEOELECTRICA ARGENTINA S.A.  
baez@na-sa.com.ar

# CONTENT

- **General overview**
- **The original Project**
- **Life Cycle of Atucha II**
- **The Project today**
- **Annex: Atucha II General Description**



Panoramic view of Atucha I and II site



# THE ORIGINAL PROJECT

**PHWR NPP 745 MWe (gross) - 692 MWe (net)**

- **Signature of Contracts:** **May 9 - 1980**
- **Parties:** **CNEA/KWU**
- **Construction Period:** **7 years**
- **Cost estimation:** **U\$S 1800 MM**

**First of a program of 4 NPP's**


# THE ORIGINAL PROJECT

## **Siemens-KWU Main Contracts (Not Turn Key):**

- **Supplies**
- **Services**
- **Warranties**
- **Transfer of technology**
- **Fuel design**

**Jointly Owned Co. (ENACE) = Architect-Engineer**

# SIMPLIFIED FLOW DIAGRAM




- 1 Reactor
- 2 Steam generator
- 3 Reactor coolant pump
- 4 Moderator pump
- 5 Moderator cooler
- 6 HP turbine
- 7 Moisture separator

- 8 LP turbine
- 9 Condenser
- 10 LP preheater
- 11 Feedwater tank
- 12 Feedwater pump
- 13 Main cooling water pump
- 14 Main condensate pump

- Reactor coolant
- Moderator
- Main steam
- Condensate/  
Feedwater
- Main cooling water



# LIFE CICLE OF ATUCHA II



# COMPLETION OF ATUCHA II

## Why?

- **Argentine needs to re-balance energy source matrix (demand is growing and natural gas restrictions)**
- **Cost of fossil fuels**
- **CO2 emissions**
- **Decision to continue with NPP's**



# PROGRESS STATUS AT THE MOMENT OF RESTARTING THE PROJECT

ITEM	PERCENTAGE INCIDENCE	ITEM PROGRESS	GLOBAL ADVANCE
	%	%	%
<i>CIVIL WORKS</i>	10,43	83	9
<i>LOCAL SUPPLIES</i>	8,92	91	8
<i>IMPORTED SUPPLIES</i>	38,00	96	36
<i>LOCAL SERVICES</i>	25,79	54	14
<i>FOREIGN SERVICES</i>	16,86	84	14
<b>TOTAL</b>	100		81

A large, rectangular object is completely covered in crinkled aluminum foil. The object is positioned in a room with a corrugated metal wall and red safety railings. A yellow arrow points from a text box to the top surface of the foil. Another yellow circle highlights a small, circular moisture indicator on the side of the foil, with a yellow arrow pointing from a text box to it. In the foreground, a small electronic device with wires is visible on the floor.

**ALUMINUM FOIL PACKAGE**

**MOISTURE INDICATOR**

Conservation of Mechanical components during the reduction period

# THE PROJECT TODAY

**Siemens-KWU: 1980 Main Contracts cancelled by mutual agreement. New Memorandum of Understanding signed on July 14, 2006:**

- **Delivery of all Project documents, including basic design and IP**
- **Final reception of former supplies and services**
- **Performance Guarantees for the Plant (Net output and heat rate)**
- **Siemens full support for conventional sector of NPP**
- **Assistance for obtaining some AREVA services**

**NASA fully responsible (as originally not Turn Key) for completion of Project**

# PROJECT MILESTONES

**AGREEMENT WITH SIEMENS  
2006**



**July**

**RESTARTING CIVIL WORKS  
2006**

**November**

**RESTARTING E. M. ERECTION  
2007**

**July**

**PRIMARY SYSTEM PRESSURE TEST**


**July 2009**

**FIRST CRITICALITY  
2010**

**March**

**GRID CONNECTION  
December 2010**

## EVOLUTION OF TOTAL PERSONNEL AT SITE





**Actual distribution of **total** personnel at site  
(End of May 2008)**

Organization	Quantity
NASA (Project Management Organization)	337
CNEA (National Atomic Energy Commission)	76
ARN (Nuclear Regulatory Authority)	7
Sub Total	420
CONTRACTORS (Including Infrastructure)	3711
Total	4131



# MAIN LICENSING AND ENGINEERING ACTIVITIES

- **Licensing review and completion of related activities**
- **Preliminary Safety Analysis**
- **Thermal-hydraulic and neutronic calculations**
- **Experimental determinations**
- **Evaluation of future fuel strategy**
- **Fractomechanics updating and verification**
- **Safety systems response to LOCA review**
- **Stress analysis completion**
- **Design review and completion in certain areas**
- **Detailed engineering completion**

# MAIN CONSTRUCTION AND RELATED ACTIVITIES

- **Recovery and development of local suppliers**
- **Civil Works**
- **Technical Revision of materials and components**
- **Electromechanical erection (Example piping)**
- **Integration of Analog and Digital I&C Systems**
- **500 kV Switchyard**
- **Remaining supplies**
- **Heavy water production**
- **First fuel load fabrication**
- **Phase A commissioning**
- **Operation and maintenance**

# Program for Technical Revision of Electromechanical Components

Agreements and/or contracts were implemented up to now with the following suppliers and/or organizations in order to perform activities related with **inspection** and **eventual refurbishment** of **stored and/or installed** components:

- Main Turbine and Generator (Siemens during assembly).
- Main Cranes (Pescarmona, Cesin, Bureau Veritas).
- Generator Leads (Siemens during assembly).
- Generator Load Breaker (ABB).
- Main Transformers (Siemens).
- Main Coolant Pumps (Andritz).
- Process Pumps and Compressors (Sterling, KSB).
- Valves (CCI-Sulzer-Herion, Tecnatom, MMA).
- Fire Dampers of ventilation systems (Trox).
- Nuclear I&C Hardware (AREVA).
- In-core instrumentation Hardware (CNEA).
- Conventional I&C Hardware (Siemens).
- Electrical Components (University of San Juan).
- Steam Generators (NASA pre-service group).
- Moderator Heat Exchangers (NASA pre-service group).
- Hydraulic Turbine (Pescarmona).
- Fuel Handling Components (AREVA, Noell).
- Filtering and cleaning systems for refrigeration service water (Lockwood during assembly).
- Elastic piping supports (Dinatecnica-Lisega).

Important infrastructure of facilities, calibration lab and workshops were constructed in order to perform part of these activities. Availability of personnel from the suppliers is the most critical issue. Very good results were obtained up to now with mechanical components (most of discoveries were related with necessary changes of parts affected by ageing like gaskets, greases and lubricants).

Inspection of bearings of installed equipment is starting now, results not yet known.



**Inspection of Main Turbine parts performed by Siemens**

**Supplier: Siemens (Germany)**



**Repeating load and functional tests of Main Crane in Turbine Building in order to evaluate actual performance**

**Supplier: Pescarmona (Argentine)**





**Inspection of Emergency Power Transformers performed by University of San Juan**

**Supplier: Trafo Union (Germany)**



**Inspection of Main Coolant Pumps performed by Andritz**

**Supplier: Andritz (Austria)**





**Inspection of ELMO Vacuum Pumps performed by NASA**

**Supplier: Siemens (Germany)**




Inspection of valves performed by CCI  
**Supplier: Sulzer (Swiss)**






**Inspection of Moderator Heat Exchangers performed by NASA  
Supplier: Pescarmona (Argentine)**



**Inspection of Hydraulic Turbine performed by NASA**  
**Supplier: Pescarmona (Argentine)**



# ATUCHA II PIPING INSTALLATION – ALLOCATION OF MAIN WORK SUB-PACKAGES



**UJA Main Coolant and Moderator Piping  
BHR/EISA (Nuclear Level 1)**

**UMA Process Piping  
SIEMENS (No Nuclear Level 3)**

**UFA Process Piping  
IECSA (Nuclear Level 2)**

**UJA-UJB Process Piping  
EISA (Nuclear Level 2)**

**UKA Process Piping  
TECHINT (Nuclear Level 2)**





**Nuclear Level 1 (Primary Heat Transport System):**  
Essener Hochdruck-Rohrleitungsbau GMBH from Germany with the  
supply of resources from local company EISA



**Nuclear Level 1 (Primary Heat Transport System):**  
Essener Hochdruck-Rohrleitungsbau GMBH from Germany with the  
supply of resources from local company EISA





**Nuclear Level 1 (Primary Heat Transport System):**  
Essener Hochdruck-Rohrleitungsbau GMBH from Germany with the  
supply of resources from local company EISA



**Nuclear Level 1 (Moderator System):**

**Essener Hochdruck-Rohrleitungsbau GMBH from Germany with the supply of resources from local company EISA**





**Nuclear Level 1 (Moderator System):**  
Essener Hochdruck-Rohrleitungsbau GMBH from Germany with the supply of resources from local company EISA



**Nuclear Level 2 (Process systems in reactor building UJA and reactor building annulus UJB): local company EISA.**





**Nuclear Level 2 (Process systems in reactor auxiliary building UKA): local company TECHINT.**



**No nuclear high qualification Level 3 (Turbine building UMA):** local branch of SIEMENS with technical support of SIEMENS USA and Germany. Direct man power provided by local companies. 35





**No nuclear high qualification Level 3 (Condenser assembly in Turbine building UMA):** local branch of SIEMENS with technical support of SIEMENS USA and Germany. Direct man power provided by local companies.





**No nuclear standard qualification Level (Hydraulic Turbine building UME): NA-SA Mechanical Construction Department. Direct man power provided by local companies.**



**Installation of Reactor Pressure Vessel**





**Civil painting application in Reactor Room**



**Arrival of Heavy Water supply to site (25 Ton vessel)**

# Integration of Analog and Digital I&C Systems

Because of the technological evolution in these aspects, the modernization of I&C systems is a normal situation in operating and DNPP`s.

After a detailed status assessment of the project situation and the definition of the scope of changes to be done in this field, the main Strategies and Management Measures adopted were:

➤ To replace some functional complexes actually using Analog systems like Iskamic B and Teleperm C with Digital systems like Teleperm XP and Teleperm XS. **This is going to be done in a first step before starting the plant.**

➤ For the implementation of this modifications purchase orders were placed to SIEMENS for **conventional systems** including engineering tasks, hardware and tools supply and training of NASA personnel.

**Main activities arising from these Strategies and Measures are:**

➤ The organization of a specific task force with an important training effort.

➤ A considerable effort in planning the engineering, construction and commissioning activities is being done in order to produce minimal impacts in the general schedule of the project.

➤ Participation of NASA experts in technical meetings organized by IAEA, complemented by visits to NPP`s were similar tasks are or were performed.



# Integration of Analog and Digital I&C Systems

In this **first step** the **functional complexes to be changed** (with the respective influence in the already installed and wired Cabinets and converting the Main Control Room in a hybrid analog-digital Control Room), are the following:

- Coolant treatment.
- Heating and Ventilation in controlled areas.
- Water and Steam Cycle.
- Auxiliary Plant Water and Steam Cycle.
- Main Cooling Water.
- Conventional Service Water Systems.


The **more important benefits** obtained from the replacement strategy are:

- Filling the gap of missing hardware out of fabrication.
- Providing spare parts for the remaining functional complexes.
- Existing cabinets and cabling to the field can be used.
- **Do not affecting safety related functions.**
- The new technology is future oriented providing long term support.

## Cabinet wiring modifications previous to integration of Analog and Digital Systems



# Main Control Room wiring modifications previous to integration of Analog and Digital Systems





# END

## THANK YOU VERY MUCH FOR YOUR ATTENTION

ESCUELA  
NA-SA DE SOLDADURA  
NA-SA  
UN PRODUCTO CERA D



Atucha II NA-SA Welding school



# ANNEX: Atucha II NPP General Description

## Notes

**As main references about Restarting of Atucha II DNPP the following Documents should be consulted:**

- **Argentine Presentation performed in the Regional Management Workshop for DNPP`s developed in Constanta Mamaia, Romania 7-11 Nov. 2005.**
- **Restarting DNPP`s - IAEA NE Series NP-T-3.4 (Annex I).**


# Technical Data

## **Type: Pressurized Heavy Water Reactor (PHWR)**

<b>Lifetime at full power:</b>	<b>32 years</b>
<b>Net Electric Power:</b>	<b>692 MW</b>
<b>Gross Electric Power:</b>	<b>745 MW</b>
<b>Coolant / Moderator Heavy Water (D<sub>2</sub>O):</b>	<b>525 Ton</b>
<b>Fuel Elements of Natural Uranium Dioxide:</b>	<b>451</b>
<b>Total Weight of each Fuel Element:</b>	<b>254 Kg</b>
<b>Total Natural Uranium Weight:</b>	<b>85 Ton</b>
<b>Coolant Pressure at Reactor output:</b>	<b>115 bar</b>
<b>Coolant Temperature at Reactor output:</b>	<b>313,8 °C</b>




# Simplified Flow Diagram




- 1 Reactor
- 2 Steam generator
- 3 Reactor coolant pump
- 4 Moderator pump
- 5 Moderator cooler
- 6 HP turbine
- 7 Moisture separator

- 8 LP turbine
- 9 Condenser
- 10 LP preheater
- 11 Feedwater tank
- 12 Feedwater pump
- 13 Main cooling water pump
- 14 Main condensate pump

- Reactor coolant
- Moderator
- Main steam
- Condensate/  
Feedwater
- Main cooling water




Moderator Cooling System








# Reactor Building




# Fuel Elements -Transport System



- 1 Refuelling machine
- 2 Shroud tube pit
- 3 Function testing position for refuelling machine
- 4 Tilting flask
- 5 Transfer tube
- 6 Tilting device
- 7 Spent fuel pool
- 8 Spent fuel pool bridge

# Fuel Elements - Storage Building




01 Montacargas  
02 Caja de escalera  
03 Piscina para recipientes de transporte

04 Piscina de almacenamiento de combustible agotado  
05 Piscina de manipulación  
06 Abertura de montaje


07 Recinto de descontaminación  
08 Zona de almacenamiento de combustible nuevo  
09 Esclusa




# Safety Passive Barriers



Barreras pasivas de seguridad




Atucha 1





Atucha 2

# Reactor Pressure Vessel









# Control Rods Layout



# Fuel Element




# Fuel Element




- 1 Closure Plug
- 2 Filler
- 3 Fuel Rod
- 4 15 Zry-Spacers
- 5 1 Inconel-Spacer



# Primary Systems - Normal Operation




# Steam Water Cycle



- 1 Steam generator JEA
- 2 Moderator cooler
- 3 Main-steam valve station LBA
- 4 H.P. Turbine MAA
- 5 Moisture separator
- 6 Separator drains pump LCT
- 7 L.P. Turbine MAC
- 8 Condenser MAG
- 9 Main-steam bypass system MAN

- 10 Main condensate pumps LCB
  - 11 Gland steam condenser MAW
  - 12 L.P. Feedwater heaters LCC
  - 13 Feedwater tank LAA
  - 14 Feedwater pumps LAC
  - 15 Demineralized water pump GHC
- GD Blowdown demineralizing system  
PAB Main cooling water system


# Layout of Safety Active Systems




Nuclear Power Plant with Heavy Water Reactor  
Layout of Active Engineered Safeguard Systems



# Plant Trains Layout



# Switchgear Building



- |    |   |    |   |
|----|---|----|---|
| 03 | Cable duct to turbine building and cooling water Structures Redundancy groups 1 – 4 | 57 | Batteries for 24 V d.c. distributions                           |
| 06 | Cable basement, redundancy group 1 – 4  | 58 | Batteries for 220 V d.c. distributions (valve actuators)        |
| 08 | Junction passage to the shafts  | 59 | Rectifiers and d.c. distributions                               |
| 33 | Intake air system   | 66 | Cabinets for control and instrumentation, redundancy groups 1-4 |
| 51 | 10/0. 66/0. 38 kV – switchgear  | 70 | Control room  |
| 52 | 10/0. 66/0. 38 kV – Emergency distribution  | 71 | Process computer room   |
| 53 | 220 V d.c. distribution (valve actuators)   |    |   |


Nov. 78

**Nuclear Power Plant with Heavy Water Reactor (600 MW Class)**  
**Switchgear Building**





# GENERAL PROJECT SCHEDULE ATUCHA I



————— Item related to Initial Critical Path